	BAGUIO WATER DISTRICT BWD Compound, Utility Road, Baguio City 2600	Document No.	ADM-PUR-F006
	PURCHASE ORDER (P.O)	Revision Date	October 29, 2019
		Revision No.	02

Nº 036320

Supplier / Contractor	: FANM ENTERPRISES, INC.	Purchase Order No.	: 36320
Contact Number	: (02) 8932-4361	Date	: September 25, 2024
Address / TIN	: Batasan Hills, Quezon City	PR No. / Abstract No.	: 09-143P-B

Gentlemen / Madam,

Please furnish this Office the following articles subject to the terms and conditions contained herein.




Place of Delivery : <input type="checkbox"/> Pick-up <input checked="" type="checkbox"/> FOB BWD Warehouse <input type="checkbox"/> Deliver at Site: _____	Purchase Order (PO) Valid Until: 30 Days Warranty: <input type="checkbox"/> Six Months <input checked="" type="checkbox"/> One Year <input type="checkbox"/> Others (please specify) _____
Date of Delivery : _____ Working Days 8-12 WEEKS _____ Calendar Days upon receipt of PO	<input checked="" type="checkbox"/> 1% Retention Required <input type="checkbox"/> Performance Bond Required (5% if in check / 50% if GSIS surety bond) <input checked="" type="checkbox"/> Subject to testing / inspection prior to payment
Delivery Term : <input type="checkbox"/> Full <input type="checkbox"/> Partial Delivery allowed	Payment Term: <input type="checkbox"/> COD <input checked="" type="checkbox"/> 30 Days <input type="checkbox"/> Others (please specify) _____

Quantity	Unit	Description / Specifications	Unit Cost	Amount
3	units	"WAGNER" Distribution Transformer 25kVA, 230V/460V X-X-X-X-X-X-X-X (Please refer to the attached sheet for complete detailed specifications)	344,478.00 ₱	1,033,434.00
Note: - Shall pass BENECO Transformer Test Standard - Shall be Polychlorinated biphenyls (PCB) free - Brand New Unit - On-Site Delivery				

01 OCT 2024

Usage / Requisitioner: For commissioning of Ferguson DW 2

Prepared by: <u>signed</u> PAUL BRAJANO C Purchasing Supervisor	Checked by: <u>signed</u> ATTY. CHANEL DOLOR D. DE GUZMAN-BITAO Admin. Division Manager	Audited by: <u>signed</u> LUZVIMIN G. RAMOS Internal Auditor	Recommending Approval: <u>signed</u> ATTY. MARY LOUISA C. TENEDERO AGM-Adm./Com./Fin.	Approved by: <u>signed</u> ENGR. SALVADOR M. ROYECA General Manager
Signature over Printed Name of Supplier		Date		
Funds Available: <u>signed</u> JELYN D. PENALES Finance Manager	Acct.: Operating / Maintenance Expense <input type="checkbox"/> CAPEX <input checked="" type="checkbox"/> Other Payables <input type="checkbox"/>			






  	BAGUIO WATER DISTRICT BWD Compound, Utility Road, Baguio City 2600	Document No.	ADM-PUR-F006
	PURCHASE ORDER (P.O)	Revision Date	February 15, 2020
		Revision No.	00

Supplier/Contractor	: FANM ENTERPRISES	Purchase Order No.	: 36320
Contact Number	: 02-8932-4361	Date	: September 25, 2024
Address / TIN	: Batasan Hills, Quezon City	PR No./Abstract No.	: 09-143P-B

Qty	Unit	Description	Unit Cost	Amount
3	units	"WAGNER" Distribution Transformer 25KVA with the following specifications: Phase: Single; Type of Installation: Overhead Type, Pole Mounted; Primary Voltage Rating: 23kV; Tap Setting: One (1) - 2 ½% tap above & three (3) - 2 ½ taps below rated primary voltage; Secondary Voltage Rating: 230V/460V; Frequency: 60Hz; kVA Rating: 25kVA; Cooling Class: OA or ONAN; Core: High- permeability, grain-oriented silicon steel or Amorphous Metal; Coil: Copper; Tap Changer: Provided with an external operating handle mounted on the tank wall; Pressure relief valve: Provided with a pull ring for manually reducing pressure to atmospheric level using a standard hot-stick Nameplate Information Serial Number BIL Class Total Weight, Kgs. Number of Phase Connection Diagram Frequency Name of Manufacturer Voltage Rating, Primary Insulation & Operating & Secondary instruction reference KVA Rating 25kVA Temperature rise, °C Type of insulation liquid (Non-PCB content) Polarity Conductor material for each Winding Percent impedance Equipment identification number Note: Shall pass BENECO Transformer Test Standard Shall be Polychlorinated biphenyls (PCB) free Brand New Unit On-Site Delivery	344,478.00	P 1,033,434.00

Total: P 1,033,434.00

Usage: For commissioning of Ferguson DW 2

Prepared by:	Checked by:	Audited by:	Recommending Approval:	Approved by:
 P.M. A. Trajano OIC-SMPO	 Atty. C.D. De Guzman-Bitao Administrative Div. Manager	 L. G. Ramos Internal Auditor	 Atty. M. T. Tenedero AGM Adm./Com./Fin./ICT	 Engr. Salvador M. Royera General Manager



RESOLUTION

Revision No. 00

Request for Quotation (RQ) No. 07-143P-B
Distribution Transformer

Signed
Engr. Salvador M. Royeca
General Manager